EUROPE'S DIGITAL IDENTITY WALLET

THE WALLET AT WORK

Preparing Your Business for
Europe's New Digital Identity Wallet

EUDI WALLET | ONBOARDING | PRIVACY | REGISTRATION

ZIRLANDIA MILKOVIC

DIGITAL IDENTITY · EUDI WALLET

THE WALLET AT WORK

Preparing Your Business for Europe's New Digital Identity Wallet

ZIRLANDIA MILKOVIC

The Wallet at Work
Preparing Your Business for Europe's New Digital Identity Wallet

© 2026 Zirlandia Milkovic. All rights reserved. No part of this book may be reproduced without written permission, except for brief quotations in reviews.

First edition, 2026. Research cut-off: 12 November 2026. British English. Companion resource: GDPRGard.eu.

This book is practical guidance, not legal, security or data-protection advice. All examples, businesses and people in worked scenarios are fictional. Laws, standards and national wallets reflect the research cut-off date and should be checked against the current legal texts and documentation.

Contents

START HERE

Educational Disclaimer 4
Introduction: The Driving Licence Nobody Wanted to Photograph 4
Who This Book Is For 6
How to Use This Book 6
The Ten-Minute Wallet Readiness Check 7

CHAPTERS

1. What the Wallet Is, and What It Is Not 9
2. Credentials and Trust: Why a Signed Answer Beats a Photograph 14
3. Customer Onboarding with the Wallet 18
4. Data Minimisation and Privacy 22
5. Relying-Party Registration 27
6. Integrating Wallet-Based Verification 31
7. When Things Go Wrong 36
8. Your 90-Day Wallet Readiness Plan 40

CLOSING

Conclusion: A Better Bargain, Built Carefully 44

APPENDICES

Appendix A: Verification-Flow Inventory 46
Appendix B: Data-Request Register 47
Appendix C: Relying-Party Registration Worksheet 48
Appendix D: Customer-Facing Wording 50
Appendix E: Integration Checklist 51
Appendix F: 90-Day Readiness Tracker 52

BACK MATTER

Glossary 53
A Note on GDPRGard.eu 54
About the Author 55
Notes and Sources 56

Educational Disclaimer

This book is practical, educational guidance for digital service providers, online businesses and the teams that build and run their sign-up, onboarding and identity-checking flows. It is not legal, regulatory, data-protection, anti-money-laundering or procurement advice, and it does not create a professional relationship between the author and the reader.

The European Digital Identity Wallet is a moving target. The law is in force, but the technical standards, national wallets, relying-party registers and supervisory expectations are still being finalised and will change after this book is printed. Dates, article numbers, specification names and version numbers reflect the research cut-off at the back of the book, and several come from secondary summaries rather than the Official Journal. Before you design, buy or promise anything, read the current text, your national authority's guidance and your providers' documentation, and take advice if you operate in a regulated sector.

Following the steps here can make your onboarding simpler, safer and easier to defend. It cannot guarantee that a regulator, a bank partner or an auditor will agree with every decision, and no checklist can replace a decision that only your lawyer, your data-protection officer or your regulator can make.

Every business, person and incident in a worked example is **fictional** and labelled as such. Real laws, standards and statements are sourced in the notes at the back, together with an honest list of what the author could not verify.

Introduction: The Driving Licence Nobody Wanted to Photograph

Marta runs Adria Drive, a fourteen-person car-rental company on the Dalmatian coast. Every summer her customers book online, arrive at a counter and wait while a tired agent photographs a driving licence, squints at a passport, retypes a date of birth and asks them to hold a phone up for a selfie. It takes eleven minutes on a good day. In July it is the reason people leave one-star reviews.

Last winter a customer from Munich asked a question that stopped her. "Can I just show you the licence from my phone wallet? I have the European one."

She could not. She did not know whether she was allowed to. She did not know what the customer would be showing her, what she would receive, what she would be permitted to keep, or what the regulator would say if she kept the wrong thing. She suspected that within two years customers like him would stop being unusual.

That suspicion is correct, and it is the reason for this book. Under the revised eIDAS Regulation, every EU Member State must make at least one **European Digital Identity Wallet** available to its citizens and residents by the end of 2026, and certain businesses will be required to accept it a year or so later.[1][2] Other businesses will not be required to accept it at all, but will find that customers expect to be able to use it.

Most writing about the wallet comes from two directions. Policy writers explain the law. Engineers explain the protocols. Almost nobody explains the middle: what a **business** has to decide, in what order, to be ready. Which of your onboarding steps could the wallet replace? What data should you ask for, and what must you stop asking for? What does registration as a "relying party" involve? Who is responsible if the credential is wrong? What do you tell the customer who has no wallet, or whose phone has died?

This book answers those questions in plain English. It does not make you a cryptographer. It gives you a defensible way to **prepare**: a map of the wallet ecosystem, a method for deciding what to ask for, a clear view of the privacy rules you will be held to, a path through registration, a realistic set of integration options, and a ninety-day plan you can start on Monday.

You will not be told that the wallet solves everything. It does not. It will not by itself make your customer checks lawful, your fraud controls sufficient or your data-protection record clean. What it can do is replace a photograph of a plastic card, taken by a stranger and stored by you indefinitely, with a small, signed, specific answer to a specific question. That is a better bargain for the customer and for you, provided you build it carefully.

Who This Book Is For

This book is written for people who own or run the sign-up and identity flow of a business that sells to people in Europe:

- **Founders and product owners** at online businesses, marketplaces, fintechs, travel and mobility firms, subscription services and platforms.
- **Operations, compliance and data-protection leads** who are asked "are we ready for the wallet?" and need something better than a vendor brochure.
- **Developers and technical leads** who will integrate wallet-based verification and want the business and legal context before they read a specification.
- **Digital service providers of every size**, from a ten-person start-up to a regional company, who do not have an identity team.

You do not need to be technical. Where a technical term matters, it is explained once, in plain language, and collected in the glossary. You do need a basic familiarity with how your own onboarding works today. If you can describe the screens a customer sees and the documents your staff handle, you have enough.

It is not written for wallet providers, national issuers or certification bodies. They have their own detailed specifications. It is also not a legal treatise. It will tell you what questions to put to your lawyer and in what order, which is usually the part people skip.

How to Use This Book

The eight chapters follow the order in which a business actually faces the decisions:

1. **What the wallet is, and what it is not.** The ecosystem, the timeline and who is obliged to do what.
2. **Credentials and trust.** What a wallet holds, who issues it, and why a signed answer beats a photograph.
3. **Customer onboarding.** Where the wallet fits into sign-up, age checks, account opening and rental-style handovers.
4. **Data minimisation and privacy.** Asking for the least you need, and the GDPR duties that come with it.
5. **Relying-party registration.** What you must declare, to whom, and how to keep it accurate.
6. **Integrating wallet-based verification.** Build, buy or connect, and what the technical flow looks like in outline.
7. **When things go wrong.** Fallbacks, failed checks, fraud, accessibility and support.
8. **Your 90-day readiness plan.**

The appendices are working documents: a verification-flow inventory, a data-request register, a relying-party registration worksheet, a customer-facing explanation, an integration checklist and a ninety-day tracker. Copy them, fill them in, and keep them current.

Look for the dark boxes headed **The rule**. Each states, in one sentence, the principle a chapter turns on. If you read nothing else, read those.

The Ten-Minute Wallet Readiness Check

Before the first chapter, answer these honestly. A "no" or "I don't know" is not a failure. It is your first to-do list item.

Question	Yes	No / unsure
Can you list every point where you ask a customer to prove who they are, or prove something about themselves?		
For each, do you know **why** you ask, and which law or risk requires it?		

Question	Yes	No / unsure
Do you know whether you are legally *required* to authenticate customers strongly (a regulated sector)?		
Do you store scans or photographs of identity documents? Do you know how long, and why?		
Could you replace any of them with a single yes/no answer (for example, "over 18")?		
Do you know which Member State's rules govern your establishment, and who your supervisory authority is?		
Do you have a named person responsible for identity-verification decisions?		
Have you ever tested the onboarding journey with a customer who has no smartphone or a broken one?		
Could you explain, in two sentences a customer would understand, what you will and will not ask the wallet for?		
Would your current identity vendor tell you its plan for the wallet, if you asked today?		

Scoring. Seven or more "yes": you are ahead, and the book will help you tighten the edges. Four to six: typical, and the chapters will fill the gaps. Three or fewer: start with Appendix A this week, because you cannot design a wallet flow around checks you have not mapped.

CHAPTER 1

What the Wallet Is, and What It Is Not

CHAPTER 1
WHAT THE WALLET IS, AND IS NOT

A bridge is a good picture for the wallet: it does not replace either bank, it lets something trusted cross between them

Start with the simplest description that is still accurate. The **European Digital Identity Wallet**, usually shortened to **EUDI Wallet**, is an app that a person holds on their own device. Into it they can load digital versions of their identity and of other facts about themselves: their name and date of birth, a driving licence, a diploma, a proof of address, a ticket. Later, when a business needs to know one of those facts, the person chooses whether to share it, and the wallet sends a cryptographically **signed** answer.[1]

The word *signed* is the heart of it. When you photograph a passport, you receive a picture. You must then decide whether the picture is genuine, and you are stuck with whatever it contains. When you receive a wallet credential, you receive data that can be mathematically checked against the issuer that created it. You know who vouched for it, you know it has not been altered, and you can ask for only the piece you need.

The people and organisations in the picture

The wallet ecosystem has more actors than a login button suggests. You will meet these roles repeatedly, so learn them now.



Who does what: the issuer vouches, the person holds, the business verifies

- **The user** (the *holder*). A person who chooses to install a wallet and to load credentials into it. Using the wallet is voluntary for individuals.[1]
- **The wallet provider.** The organisation that supplies the wallet app. Each Member State must offer at least one wallet, either made by the state or by a mandated or recognised provider. Wallet providers are meant to be unable to see what the user shares or to track where the wallet is used.[1]
- **The PID provider.** PID stands for **person identification data**: the core identity record, such as name and date of birth, issued by or on behalf of a Member State.
- **Attestation providers.** Anyone who issues a verified fact about a person: a licensing authority, a university, an employer, a bank. These facts are called **electronic attestations of attributes**. Some are issued by *qualified* providers and carry stronger legal weight.
- **Relying parties.** This is **you**. A relying party is any business or public body that asks a wallet for data in order to deliver a service. The regulation uses the phrase *relying party* and treats it as a role with its own obligations, which is why Chapter 5 is devoted to it.[3]
- **Supervisory bodies and registers.** Each Member State designates who supervises the ecosystem and keeps the national register where relying parties declare what they intend to request.

The roles can overlap. A bank can issue an attestation about an account and also rely on the wallet to open one. A university can issue a diploma and rely on a PID to enrol a student. What matters is that you

know, in each flow, which role you are playing.

What the wallet is not

Misunderstandings cost businesses money, so be direct about the limits.

It is not a replacement for knowing your own legal duties. The wallet can deliver trustworthy data. It does not decide whether you are allowed to open an account, whether a customer is on a sanctions list, or whether your anti-money-laundering procedures are sufficient. Those obligations sit with you. Whether and how a wallet credential can satisfy a particular customer-due-diligence requirement is a question for your regulator and your sector rules, not for this book.[9]

It is not compulsory for people. Individuals cannot be forced to use it, and you may not treat a refusal to use it as a reason to deny them a service where an equivalent route is required. Plan for customers who will never install a wallet.

It is not a universal login. The wallet is built to share *attributes and credentials*. It can be used to authenticate, but it is not designed to become a new social login that follows people across the web.

It is not one app. It is a framework. Member States will provide their own wallets, built to common technical rules so that a Croatian wallet can be read by a Dutch business. Expect small differences in look, setting and support.

It is not finished. The legal text is settled. The technical standards, national implementations and the registers are still being completed and tested. A sensible business prepares now, builds in small steps and avoids committing to a final design until the specifications you depend on are stable.

The timeline, and who has to do what

The regulation that created the wallet, Regulation (EU) 2024/1183, entered into force in May 2024 as an amendment to the original eIDAS Regulation.[1] Several dates matter to a business.



The dates that matter, from the law coming into force to acceptance duties for regulated businesses

- **By the end of 2026**, each Member State must make at least one wallet available. Sources give 24 December 2026 as the working date, with the exact figure depending on when the first implementing acts took effect. The Commission has itself acknowledged that not every country will arrive with a fully featured wallet on day one.[2]
- **Around a year later**, the duty to **accept** the wallet begins for certain private relying parties. These are, broadly, businesses that are already required by EU or national law, or by contract, to carry out *strong user authentication* of customers. Examples named in the legislation include banking, financial services, transport, energy, health, telecommunications, education and digital infrastructure.[2]
- **Very large online platforms** are expected to accept the wallet when a user asks to authenticate with it, on a voluntary-use basis, on an earlier timetable than the general acceptance duty.[2]
- **Everyone else** has no obligation to accept the wallet at all. You may choose to, and for a growing share of customers you will want to.

That last group is the large majority of businesses reading this book. Your question is not "are we forced?" but "is it worth it, and what is the least risky way to start?" Chapter 8 answers that with a plan. If you are in a regulated sector, your question is "by when, and for which flows?" and the answer comes from your own legal analysis, not from this chapter.

The rule: Know which of three situations you are in: required to accept, likely to be asked, or free to choose. Each leads to a different plan.

Why bother if you are not required to

Three reasons recur, and none is about being fashionable.

It removes data you should not be holding. Every scanned passport in your storage is a liability: a breach target, a retention question and a subject-access request waiting to happen. A wallet answer can say "this person is over 18" without handing you a birth date, a photograph or a document number.

It reduces friction where it costs you most. Marta's counter queue is the example, but the same applies to age-gated sales, account opening, and any sign-up where customers abandon the form at the identity step.

It improves the quality of what you receive. A signed credential from an official issuer is harder to forge than a photograph of one. Fraud that relies on edited images and borrowed documents has a harder time against cryptography.

None of these is free. You will spend effort on integration, registration, privacy documentation and support. The next chapters show where that effort goes, so you can decide with your eyes open.

CHAPTER 2

Credentials and Trust: Why a Signed Answer Beats a Photograph



A credential in the wallet is closer to a sealed card than a photograph: the seal is the point

To design a good flow you need a working picture of what is actually inside a wallet and why you can trust it. You do not need the mathematics. You need four ideas.

Idea one: credentials are issued, held and presented

Three verbs describe the whole lifecycle.

1. **Issued.** An issuer, such as the authority that grants driving licences, creates a credential and signs it. The signature is the issuer's seal.
2. **Held.** The person receives the credential into their wallet, where it stays on their device, protected by their device security.
3. **Presented.** When a business asks, the person approves, and the wallet sends a presentation proving the credential is genuine and unaltered, and proving it belongs to them.

You, the business, take part only in the third step. You never see the first two. That is a relief, and it is also a risk: you are relying on parties you cannot inspect. Which is why the next idea matters.

Idea two: you verify the seal, not the person's word

When a presentation arrives, your software checks three things:

- **Is the signature valid?** Was this credential really created by the issuer it claims?
- **Is the issuer trusted?** Is that issuer on the trusted lists that the framework maintains? A perfectly valid signature from an unknown issuer means nothing.
- **Is it still valid?** Has it expired, been revoked, or been suspended?

If you were buying this as a service, these checks are what the vendor does for you. If you were building, they are what your developers implement with a library. Either way, you should be able to say in one sentence how each is done. "The vendor handles it" is not an answer a regulator will accept on its own.

Idea three: different kinds of credential, different weight

Not everything in a wallet is equal. Keep three categories apart.



Three kinds of credential, and how much each should count for in your process

Person identification data (PID). The core identity record issued under a Member State's authority. It carries a small set of mandatory attributes about the person, such as family name, given names, date of birth, place of birth and nationality, with optional extras.[4] This is the closest thing to a digital passport page.

Qualified electronic attestations of attributes. Facts issued by a qualified trust service provider or a public body: a diploma, a professional licence, a driving licence in some countries. These have the strongest legal footing after PID.

Other electronic attestations of attributes. Facts issued by any organisation: a membership card, a loyalty status, an employer letter. They are useful, but your decision about how much to rely on one is a **business** decision. A gym membership credential proves membership, and nothing else.

Each of your flows should name which category it needs. "We need to know this person is over 18" is a PID-type question, or one a trusted age attestation can answer. "We need to know this person may drive" is an attestation question. "We need to know this person is a customer of ours" is probably yours to answer already, with no wallet involved.

Idea four: selective disclosure is the feature that changes your design

In the paper world, showing a licence to prove your age also shows your address, your licence number and every category you hold. You cannot hide part of the card. In a wallet, a credential can be built so that the person reveals **only some of its attributes**, or even only a derived answer, while you can still verify the signature on the whole.[4]



Selective disclosure: the wallet answers the question asked, and keeps the rest to itself

The wallet's initial credential formats, described in the architecture framework, are two: an **SD-JWT**-based format designed for selective disclosure, and the **mobile document (mdoc)** format from the ISO 18013-5 standard that also drives digital driving licences.[4] You do not need to choose between them as a business. Your integration, whether built or bought, will usually handle both. What you need to understand is the consequence: **the technology lets you ask for less, and the law will expect you to.**

> **The rule:** If a flow can be answered with a yes/no or a single attribute, designing it to ask for the whole document is not just wasteful. It is the thing a supervisory authority will notice.

Where trust actually comes from

A last point, because it is the one people get wrong. The wallet does **not** make a person trustworthy. It makes a *claim* trustworthy: "this authority says this person's date of birth is this." Whether the person standing at your counter or typing into your form is the *same person* as the credential describes is a separate question, answered by how the wallet binds the credential to the holder and by what extra checks your risk level requires.

For a rental handover that matters a great deal. A driving-licence credential proves a licence exists. Your process must still decide whether the person collecting the car is its holder. Wallet-based flows usually make this easier, because the credential is tied to a device and an unlock step. But "easier" is not "automatic", and the risk assessment in Chapter 3 is where you decide how far to trust it.

CHAPTER 3

Customer Onboarding with the Wallet

The front of the queue is where identity checks cost the most, in time and in goodwill

Onboarding is where most businesses will first meet the wallet, because it is where identity checks live. This chapter shows how to look at your existing flow, decide which steps the wallet could replace, and redesign without breaking the journey for everyone who has no wallet.

Step one: map what you ask for today

You cannot improve what you have not drawn. For each point in the customer journey where you ask a person to prove something, write down four things:

- **What you ask for** (the document, the field, the photograph).
- **Why you ask** (a legal duty, a contract term, a fraud control, habit).
- **What you do with it** (check and discard, store, share with a partner).
- **What happens if the customer cannot provide it** (decline, manual review, alternative).

Adria Drive's list, once Marta wrote it down, surprised her. She was collecting a passport scan, a licence scan, a selfie and a billing address. She stored all four for the full length of the rental year "in case". Only

two of those had a clear reason. That alone justified the exercise. Appendix A is a blank version for you to fill in.

Step two: sort each check into a question type

Once mapped, almost every check falls into one of five types. The type tells you how the wallet might help.

Question type	Example	Wallet fit
Identity match	"Is this the person named on the booking?"	Strong: PID plus a binding to the holder
Age threshold	"Are they over 18, over 21?"	Very strong: a yes/no answer needs no birth date
Entitlement	"May they drive this category of vehicle?"	Strong where an attestation exists, such as a driving licence credential
Address or residence	"Do they live in the country we serve?"	Variable: depends on whether address attributes are available and reliable
Relationship or status	"Are they a student, a member, an employee?"	Depends on whether an issuer offers a credential

You will notice that many checks do not need the **identity** at all. They need a fact. That is where the wallet helps most, and where the next chapter's privacy rules begin to bite.

Step three: decide how far to trust the credential

For each flow, set the **assurance** you need. A newsletter sign-up needs none. A bike rental needs some. A regulated account opening may need the highest level your sector rules allow. The wallet framework lets credentials be presented at different levels of assurance, and your risk decision should match your real exposure, not the most impressive-sounding setting.

Three questions help:

1. **What is the worst realistic loss** if a person lies about this? Money, safety, legal liability?
2. **What else do we check** around it? Payment method, device, behaviour, a signature at handover?

3. **Does a regulator or partner dictate the level** (a card scheme, a bank, an insurer)? If so, their rule wins.

Step four: redesign the journey with a wallet option, not a wallet requirement

The most common mistake is to treat the wallet as the new front door. It is not, and for years it will not be. Design the wallet as the **fast lane** and keep the existing route as a real alternative.



A wallet fast lane alongside the existing route, so no customer is turned away

A good wallet-aware flow has four parts:

1. **A clear choice at the identity step.** "Share from your wallet" beside "Upload a document". Both visible, neither hidden.
2. **A short, honest explanation** of what will be requested and why, shown before the wallet opens. Appendix D gives wording.
3. **A fast confirmation** after the wallet responds, showing the customer what you received, not a spinner.
4. **A graceful fallback** that does not lose the customer's progress if the wallet fails.

For a handover-based business like Adria Drive, there is a fifth part: the **counter or kiosk**. A customer can present the wallet in person, by tapping or scanning, and the agent's device receives only the licence validity and category. No photograph, no retyping, no copy. The queue shortens, and nothing sits on a shared tablet at the end of the day.

Case: three fictional businesses, three designs

Adria Drive (car rental). Asks the wallet for: driving-licence validity and categories, and a match between the licence holder and the booking name. Does not ask for the address, the document number or the place of birth. Keeps a record that the check passed, with date, outcome and issuer, not the document itself.

Fenix Fitness (age-gated product sales). Asks only: "over 18: yes or no". Keeps nothing but the yes/no and the time. Has no birth dates in its database, and so nothing to lose in a breach.

Klarheit Energy (a regulated energy supplier). Is within the sectors where acceptance may become compulsory. Treats the wallet as a mandatory option, builds against the registered intended use from the start, and keeps its existing document route for customers without a wallet, because its regulator requires one.

All three used the same wallet. They asked different questions, stored different things and carried different obligations. That is the point: **the wallet is a channel, and your design decides what flows through it.**

Pitfalls that recur

- **Mirroring the paper process.** Asking the wallet for every field the scan showed. You have missed the benefit.
- **Hiding the alternative.** Making the wallet the only visible choice, then discovering that customers without one leave.
- **Forgetting the second device.** A flow that opens a wallet on the same phone as the browser works one way; a flow on a desktop with a phone nearby works another. Test both.
- **Ignoring the human at the counter.** Staff need a one-page guide on what appears on screen and what to do when it does not.
- **Storing the result as if it were the document.** Record the *outcome* of the check. Do not rebuild the scan you were trying to stop holding.

> **The rule:** Build the wallet as a fast lane next to the existing route, and ask it only the question you need answered.

CHAPTER 4

Data Minimisation and Privacy

Every scan you keep is a box on a shelf somebody will one day ask you to open, and to account for

The wallet was designed around privacy. That sounds like a comfort to the business, but it is better understood as a **constraint** placed on you. The technology makes it easy to ask for little. The law makes it expected. This chapter explains what is asked of you, in the order a regulator would ask it.

Minimisation is now a design feature, not a slogan

Under the GDPR you may process only personal data that is **adequate, relevant and limited to what is necessary** for the purpose.[5] For years that sentence was hard to enforce, because the only practical way to check an age was to look at a document, and you cannot unsee a birth date. The wallet changes the position. If a yes/no answer is available, collecting a birth date is no longer a practical necessity. It is a choice.

The same check, asked two ways: what you needed against what you collected

The eIDAS framework reinforces this in its own text. A relying party must not request more data than it declared when it registered, and the declared purpose must be specific enough for the request to be judged necessary and proportionate.[3][6] So minimisation is enforced twice: by data-protection law and by the wallet ecosystem itself.

Put into practice, apply a simple test to every attribute you plan to ask for:

1. **Name the purpose** in one sentence ("to confirm the renter may drive a category B vehicle").
2. **Name the smallest attribute** that serves it ("licence category B valid: yes/no", not "full licence record").
3. **Ask whether a derived answer is possible** ("over 21" instead of a birth date).
4. **Write down what you will do** if the customer declines to share it.

If you cannot complete step one, the attribute is not necessary. If step four has no answer, you have a flow with no fallback, which is Chapter 7's problem.

The GDPR duties that come with the wallet

Receiving data from a wallet is still processing personal data. Nothing about the technology cancels your obligations. Map the familiar duties to the new flow.

The GDPR duties that apply to a wallet flow, and the question each one asks you

Lawful basis (Article 6). Know which basis supports each request: contract, legal obligation, legitimate interest or consent. Do not assume that because the customer pressed "share", you have consent. Consent must be freely given, and it is often not the right basis for a check you need to carry out in order to supply the service.

Transparency (Articles 13 and 14). Tell people what you are asking for, why, how long you will keep the outcome and who sees it, *before* they approve in the wallet. The wallet will show the request, but your notice is still your responsibility.

Data protection by design and default (Article 25). The strongest argument that you comply is a flow that was built to ask for little and keep less. The weakest is a flow that collected everything and added a deletion job later.

Storage limitation (Article 5(1)(e)). Decide, in writing, how long the **outcome** of a check is kept, and delete accordingly. If the wallet response is not needed after verification, do not keep it.

Security (Article 32). The response contains personal data in transit and, if you log it, at rest. Keep it out of ordinary application logs, analytics tools and support tickets.

Processors and international transfers (Articles 28 and 44 onward). If an identity provider, integrator or hosting service handles wallet responses for you, you need a data-processing agreement and an

understanding of where the data goes. "The vendor is European" is a claim to check, not a fact to assume.

Impact assessment (Article 35). Large-scale processing of identity data, or novel technology used in a way that could affect people significantly, may require a DPIA. Even where it is not strictly required, writing a short one is the best way to prove you thought about it. Appendix B includes a data-request register that forms the core of one.

What the wallet gives you that you can use

A handful of the wallet's own protections are worth knowing, because they shape what your customers will expect.

- **The person sees what is requested and chooses what to share.** They are shown who is asking and, where registration data is available, what the registered purpose is.
- **Pseudonyms.** A person can, in appropriate cases, use a pseudonym instead of their real name for services that do not need it.[1]
- **A dashboard.** Wallets are meant to let the user see their history of sharing and to report a relying party that asks for too much to the data-protection authority.[1]
- **No tracking by the provider.** The wallet provider is not meant to learn where the user shares credentials.

The last two matter to you directly. A customer who feels over-asked can complain with a few taps. A business that asks for more than it declared is not just breaking a rule; it is giving the customer the means to prove it.

Special categories and the biometric question

Two things need extra care.

Biometrics. The wallet itself may unlock with a fingerprint or face. That match happens on the person's device and is not shared with you. If **you** perform your own face matching, for example comparing a selfie to a portrait attribute from the credential, you are processing biometric data. When it is used to uniquely identify a person, it is special-category data under Article 9, which needs its own legal

ground and strong justification.[5] Decide whether you need it at all. In many wallet flows the cryptographic binding to the holder does the job a selfie used to do.

Sensitive attributes. Some credentials, such as health-related or disability-related ones, are special-category data by nature. If your business has no clear legal ground to receive them, do not ask for them, and design your request forms so that nobody on your team can add them casually.

A privacy notice customers will actually read

Appendix D gives a model. The principles:

- **Say what you ask for in plain words**, before the wallet opens.
- **Say what you keep**, and for how long.
- **Say what happens if they decline**, and show the alternative.
- **Keep it to a few lines** on the screen where the decision is made, with the detail one tap away.

> **The rule:** Ask for the smallest attribute that answers the question, keep only the outcome, and tell the customer both before they approve.

CHAPTER 5

Relying-Party Registration

A register is an ordinary, unglamorous list. Being on it correctly is what lets the rest of the system trust you

Every business that wants to request data from a wallet is expected to **register** as a relying party in the Member State where it is established. [3] This is the chapter most businesses will want to skip, and the one that quietly decides whether the rest works.

What registration is for

Registration exists so that a wallet can show the user *who is asking and for what*, and so that regulators can check that what is requested matches what was declared. It turns "a website asked for my data" into "a named, registered business asked for these attributes for this stated purpose". It is how the ecosystem keeps the promise of a person staying in control.

Where it applies, the key obligations are these, as they appear in the Commission's implementing rules and the amended regulation:

- **Registering** in your Member State of establishment, with identification of your organisation.[3]
- **Declaring the intended use**, meaning the services you will provide using the wallet and the purpose of each request.

- **Declaring the precise list of attributes** you intend to request for each intended use.[3]
- **Not requesting anything beyond what you declared.** Asking for undeclared data is described as a ground for cancelling the registration.[3]
- **Keeping your entry accurate**, which includes updating it when your use changes and withdrawing it when you stop.

Registration may be carried out through an automated process in the national system. Member States are expected to have their relying-party registers operating at roughly the time wallets become available, but the practical state of play will differ by country and by month.[2]

The registration pack: what to prepare

You cannot fill a form well on the day. Prepare these pieces first. Appendix C is a worksheet that collects them.



The six pieces of a registration pack, assembled before the form is opened

1. **Legal identity.** Your registered name, number, address and the Member State of establishment. If you operate in several, decide where your main establishment is and check the rule with your adviser.
2. **A named responsible contact.** Someone who will receive notices and keep the entry current.

3. **Intended uses, one by one.** Not "customer verification" but "age check at checkout for restricted goods" and "driving-licence check at vehicle handover". Specific is better, because specific is what a reviewer can approve.
4. **For each use, the attribute list.** The exact attributes, taken from your Chapter 4 test. Remember that everything you will ever ask for must be on the list in advance.
5. **The justification.** A sentence or two per attribute on why it is necessary and proportionate. The European Data Protection Supervisor has stressed that intended-use descriptions need to be specific enough to let someone verify that the requested attributes are necessary.[6]
6. **Your privacy information.** The link to the notice customers will see, and the contact for data-protection questions.

Three registration mistakes to avoid

Registering a long, generous list "to be safe". Asking for broad permissions up front looks prudent. It also looks like exactly the over-collection the rules are designed to stop, and it invites questions. Register what you actually use. Update when that changes.

Registering once and forgetting. A new feature that asks for one extra attribute, shipped without updating the register, is a request for undeclared data. Tie registration changes to your release process, as Chapter 6 shows.

Treating registration as the vendor's job. If an integrator or identity provider requests wallet data on your behalf, whose registration is it, and whose name does the customer see? Settle this in writing. Responsibility does not travel with the contract unless the contract says so.

Registration certificates and what the wallet shows

Alongside registration, the framework describes a **registration certificate**, a signed data object that tells wallets what a particular relying party has registered to request.[3] A wallet can use it to compare what you are asking for against what you declared and to warn the user when the two differ. Whether certificates are issued, and

in what form, depends on the Member State, so do not build a design that assumes either way. Build the discipline instead: your requests should always match your declaration, certificate or no certificate.

There is an additional authentication element to know. When your system talks to a wallet, it identifies itself using credentials issued to you, often called **access certificates**, so that the wallet can verify it is really you. In a build-it-yourself integration you manage them. In a bought integration your provider usually does, and you should know whose name is on them.

Keeping the entry alive

Registration is a living record, not a certificate on the wall. A sound routine is small:

- **A named owner** for the entry.
- **A quarterly review** comparing the register to the data-request register in Appendix B.
- **A change rule:** no release that adds, removes or changes a wallet request ships without a registration check.
- **A withdrawal rule:** when a use is retired, the entry is updated.

And a warning on timing. The detailed rules on registration have been the subject of amendments and draft changes during the preparation of this book, and the application date of some provisions is reported differently by different sources.[3] Treat any date in this chapter as a pointer to check, not a fact to plan around.

> **The rule:** Register exactly what you request, no more, and make a registration check part of every change to your wallet requests.

CHAPTER 6

Integrating Wallet-Based Verification



Integration is mostly ordinary product work: a request, a response, a decision and a record

This chapter is for the person who will own the integration, technical or not. It explains the shape of the flow, your three realistic routes, and the questions that stop you from buying or building the wrong thing. It deliberately stops short of code, because the specifications are still moving and code printed here would age quickly.

The flow in outline

Whatever you choose, the sequence is the same.



The six moments of a wallet check, from your request to your recorded outcome

1. **Your service creates a request.** It states which attributes you want, from which kind of credential, with a one-time value so the response cannot be replayed later.
2. **The customer's wallet receives it.** On the same phone, through a link or button. On a desktop, usually through a QR code the customer scans with their phone. At a counter, through a tap or a scan.
3. **The wallet shows the customer** who is asking and what is requested, and asks them to approve with their device unlock.
4. **The wallet returns a presentation.** The response carries the signed data and proof that it belongs to the holder.
5. **Your service verifies it.** Signature, trusted issuer, validity, binding to the request, status.
6. **You decide and record.** Pass, fail or refer to a person. Keep the outcome, not the raw response, unless a rule says otherwise.

The protocols behind steps one to four are open standards from the OpenID Foundation: one for **issuing** credentials into a wallet and one for **presenting** them to a relying party.[4] Alongside them, the

framework profiles two credential formats and a security profile to keep implementations interoperable. You will hear the names. Your job is to ask your provider or team which versions they support and whether they have tested against the European reference implementation and recent interoperability events, not to memorise them.

Same device or another device?

A detail that causes most early disappointment. A customer on a phone browser moves to the wallet app and back. A customer on a laptop scans a code with the phone. A customer in a shop taps. Each path has its own failure points: an app not opening, a code that times out, a browser that loses state when the wallet app takes over. Build and test all three, with real wallets and real handsets, and keep the progress of the customer's sign-up when they go away and come back.

Your three routes



Three routes into wallet verification, and who carries which responsibility in each

Route A: Connect through your existing identity provider. If you already use an identity-verification or authentication vendor, ask for their wallet roadmap. The advantage is speed and one contract. The risks are dependence on their schedule, reduced visibility of the detail, and the registration and responsibility questions in Chapter 5.

Route B: Use a specialist wallet-verification service. A provider that exists to handle the receiving side of the wallet on your behalf: it creates requests, verifies presentations and returns a clean result. You write a small integration and keep a clear contract. Compare them like any processor: where data is processed, what is retained, what certifications are held, and what happens when the specifications change.

Route C: Build it yourself. Appropriate if identity is core to your product and you have security engineers. You gain control and carry the full burden: tracking specifications, maintaining certificates, managing trust lists, handling status checks, staying interoperable, and passing assurance reviews. Few small businesses should choose it for a first launch.

Most readers should choose A or B for a first version, keep the design modular, and revisit later. "Modular" means one place in your code where a wallet result becomes a yes, no or refer-to-human, so that changing vendor does not mean changing your product.

Twelve questions to ask any vendor

Put these in writing before signing. A good provider will answer them plainly.

1. Which wallets and credential formats do you support today, and which are on the roadmap with dates?
2. Have you tested against the EU reference implementation and recent interoperability events? Show results.
3. Whose name and certificates appear to the wallet when a request is made?
4. Who registers as the relying party, and who keeps the entry accurate?
5. Where is wallet response data processed and stored, and for how long?
6. Can we request attributes individually and set the minimum we need per use?
7. Which trusted lists do you check, and how quickly do you pick up changes?
8. How do you handle revoked or suspended credentials?

9. What do we receive: raw data, a signed result, or just pass or fail?
0. What is your incident process if a specification flaw or a certificate problem is found?
1. What are your uptime commitments, and what is the failure behaviour?
2. What happens to our data and our integration if the contract ends?

Security in a sentence each

- **Use a fresh one-time value in every request**, and reject responses that do not match.
- **Keep wallet responses out of logs, analytics, error trackers and support tools.**
- **Verify on the server**, never only in the browser.
- **Protect your own certificates and keys** as production secrets, with rotation and expiry alerts.
- **Rate-limit and monitor** the endpoint, as you would any identity endpoint.
- **Record outcomes with enough context** (time, flow, result, issuer) to investigate, and nothing more.

Testing like a business, not a lab

Test with **real people on real phones**, including older devices and the least technical person on your team. Count how many reach the end without help. Time them against the old process. Check what customers say aloud when the wallet opens. These observations are worth more than any specification checklist, and they are the evidence you will want when deciding whether to expand.

> **The rule:** Keep the wallet behind one decision point in your product, choose the lightest route that carries your risk, and test with real customers on real phones.

CHAPTER 7

When Things Go Wrong

A dead phone at a counter is not an edge case. It is Tuesday

A wallet flow that works for the cooperative customer on a new phone is a demo. A flow that survives everything else is a service. This chapter lists the ways things fail and what a prepared business does about each.

The six failures you will meet



The six most common failures, and the response that keeps the customer and the control

1. The customer has no wallet. Most customers, for some time, will not. This is not a failure of the customer. Your alternative route is part of the product, with the same clarity, speed and tone as the wallet route. Do not make people feel they are being punished for using paper.

2. The wallet is not supported. A customer's wallet may come from another country, use a newer version, or fail on an older phone. Show a clear message, offer the alternative route immediately, and **log the failure** so you can see patterns.

3. The check fails. A credential is expired, revoked, or from an issuer you do not trust, or the name does not match the booking. Say plainly what failed in words the customer can act on ("this licence has expired") without disclosing more data than needed. Offer a referral to a person, not a dead end.

4. The customer's device is lost, broken or flat. Passing a recovery problem to your helpdesk is common. Prepare a script: what the person can do, what you can accept as an alternative proof, and what you must not accept. The cautious rule from any account-recovery process applies: **do not let your fallback be weaker than the control it replaces.**

5. Fraud. Wallets make some fraud harder and displace the rest. Expect borrowed devices, coerced users, fake relying-party prompts and attempts to socially engineer your staff into skipping the check "just this once". Train staff that the exception route is where attackers go. Keep a record of overrides, and review them.

6. Something inside your own system breaks. A trusted-list update fails, a certificate expires, a library changes. Monitor the check as a service, with alerts and a human who knows the next step.

Accessibility is part of verification

A wallet flow that cannot be used by a person with low vision, limited dexterity or a hearing difficulty is not a faster route. It is a barrier with a better logo. The European Accessibility Act now sets duties for many consumer-facing digital services, and the wallet's own design aims for

accessibility. Check your own screens, prompts, timeouts and error messages with assistive technology, and test with people who use it. Keep an assisted route that does not depend on a smartphone at all.

Support: the script behind the screen

Give your support team three one-page tools:

- **What the customer sees at each step**, with screenshots.
- **The four most common problems** and the exact response to each.
- **What they may not do**: accept a photo sent over chat instead of a check, bypass a failed verification because the customer is cross, or ask the customer to read data aloud that the wallet should have sent.

Data subject requests and incidents

Treat wallet-derived data like any other personal data in your **access, correction and deletion** processes. The cleanest answer to a request is a short record: the outcome, the date and the flow. If you kept more, you will have more to disclose, protect and explain.

If you suspect that wallet responses have leaked through a log, a misconfigured integration or a vendor fault, run your normal breach process: contain, assess, and decide within the 72-hour clock whether the authority must be told. Practise the first hour before you need it.

Measure what matters

Four numbers tell you most of what you need:

- **Completion rate** on the wallet route against the old route.
- **Time to complete** each.
- **Fallback rate**, meaning how many wallet attempts end in the alternative route.
- **Manual-review rate** and the reasons.

If completion is higher and fallback is low, the wallet is helping. If fallback is high, the problem is usually the flow, not the customer.

The rule: Every wallet step needs a safe, equally respectful alternative, and your fallback must never be weaker than the control it replaces.

CHAPTER 8

Your 90-Day Wallet Readiness Plan

A street at blue hour: you do not need to see the whole route, only the next corner

You have the map. This chapter turns it into ninety days of work, in three phases that build on one another. The plan is deliberately modest. A small business can finish it alongside normal work.



Three phases over ninety days: understand, decide, pilot

Days 1 to 30: Understand

Week 1: Appoint and scope. Name one owner for wallet readiness. List every flow where you ask a customer to prove something. Fill in Appendix A.

Week 2: Classify and minimise. For each check, assign a question type (Chapter 3) and apply the minimisation test (Chapter 4). Fill in Appendix B. Mark the checks where a yes/no answer would suffice.

Week 3: Know your obligations. Decide which of the three situations you are in: required to accept, likely to be asked, or free to choose. Take advice for any flow in a regulated sector. Identify your supervisory authority and the national register for your Member State of establishment.

Week 4: Ask your vendors. Send the twelve questions from Chapter 6 to your current identity or authentication providers. Record the answers, and the silence.

Outcome of the month: a mapped inventory, a data-request register, and a written view of your legal position.

Days 31 to 60: Decide

Week 5: Pick the pilot flow. Choose one flow where the wallet clearly helps, with moderate risk and a good fallback. An age check or a counter handover is usually better than account opening.

Week 6: Choose the route. A, B or C from Chapter 6, with the reasons written down. Compare two vendors on the twelve questions.

Week 7: Draft the registration pack and notice. Complete Appendix C. Draft the customer wording in Appendix D. Complete a short DPIA built from your register.

Week 8: Design the fallback and the support script. Define what happens when the wallet is unavailable or the check fails. Brief support. Write the one-page staff guide.

Outcome of the month: a chosen pilot, a chosen route, a registration draft, a notice and a support plan.

Days 61 to 90: Pilot

Week 9: Build or configure. Integrate in a test environment. Work through Appendix E with your technical lead.

Week 10: Test with real people. At least ten people, at least three on older devices, at least one using assistive technology. Record time, completion and comments.

Week 11: Limited launch. Open the wallet option to a small share of customers or a single location. Watch the four numbers from Chapter 7 daily.

Week 12: Review and decide. Review results against the old route. Decide whether to expand, adjust or pause. Update the register, the notice and the registration entry to match what you actually do.

Outcome of the quarter: a live, small, monitored pilot, and a decision based on evidence.

Decisions to make along the way

Decision	Who decides	By when
Are we required to accept the wallet, and when?	Owner with legal adviser	Day 21
Which flow to pilot?	Product owner	Day 35
Build, buy or connect?	Product and technical lead	Day 45
What do we register and who owns it?	Compliance or DPO	Day 55
What is the fallback for each flow?	Operations	Day 58
Expand, adjust or pause?	Owner	Day 90

What to watch after day 90

The ecosystem will keep changing. Assign someone to follow four things, monthly at first: **national wallet availability** in the countries you serve, **changes to the registration rules**, **updates to the technical specifications** your vendor relies on, and **guidance from your supervisory authority**. A thirty-minute monthly review is enough to keep a small business out of trouble.

> **The rule:** Start with one flow, learn from real customers, and let the evidence, not the excitement, decide how far you go.

Conclusion: A Better Bargain, Built Carefully

An open door is only an invitation. What matters is what you do once people walk through it

Marta did not rebuild Adria Drive's business around the wallet. She did something smaller and wiser. She mapped what her counter asked for and found two checks she had no reason to keep. She wrote down the one question the wallet could answer at handover. She registered that purpose, told customers plainly, kept the old route open and measured. In her first summer of testing, the Munich customer who had asked the question was through the counter in under two minutes, and nothing about him stayed on her shared tablet.

That is the whole strategy in one story. The wallet is not an event to survive or a trophy to collect. It is a chance to replace a risky habit, collecting images of documents, with a better one: asking a precise question and receiving a precise, verifiable answer.

The businesses that benefit most will not be the earliest or the loudest. They will be the ones that:

- **know what they ask for and why**;
- **ask for the least that answers the question**;
- **register and declare honestly**, and keep the declaration true;

- **keep an equally good route for people without a wallet**;
- **choose the lightest integration that carries their risk**; and
- **learn from real customers before they scale.**

You do not need to finish today. You need to start with a list, one owner and one flow. Begin with Appendix A.

APPENDIX A

Verification-Flow Inventory

One row for every point where you ask a customer to prove who they are or something about themselves. Include staff-handled steps at counters and by phone. Review every quarter. Question type: **I** identity match, **A** age threshold, **E** entitlement, **R** residence, **S** status or relationship.

Flow / step	What we ask for today	Why (law, contract, risk)	Type	Kept? For how long?	Wallet could help?

Questions to answer for each row

- Which law, partner or contract requires this check, if any? _____
- Could a yes/no or single attribute replace the document? Yes / No
- What happens today if the customer cannot provide it? _____
- Who is responsible for this check? _____

APPENDIX B

Data-Request Register

This is the single most useful page in the book. It is the core of your DPIA, your privacy notice and your registration entry. Keep it in step with what your product really requests.

Intended use	Attribute requested	Why necessary (one sentence)	Lawful basis	Kept as	Retention	Who sees it

The test for every row

- ☐ The purpose is stated in one sentence.
- ☐ A smaller attribute or a derived answer was considered.
- ☐ We keep the outcome, not the raw response.
- ☐ The retention period is written and deletion is automatic.
- ☐ The customer is told before they approve.
- ☐ The attribute appears in our registration entry.

APPENDIX C

Relying-Party Registration Worksheet

Complete this before you open the national registration form. Check the current requirements of your Member State of establishment, because forms and fields vary.

Item	Our entry
Legal name and registration number	
Member State of establishment	
Registered address	
Named responsible contact and deputy	
Data-protection contact (DPO or equivalent)	
Supervisory authority	
Link to privacy notice shown to customers	
Who operates the technical integration (us / provider)	
Whose certificates identify us to the wallet	

Intended uses

Use	Service it supports	Attributes (exact list)	Justification

Before you submit

☐ Every attribute in our product appears here, and nothing else.

- ☐ A named person owns the entry and its changes.
- ☐ Our release process includes a registration check.
- ☐ The responsibility split with any provider is in the contract.
- ☐ We know how to update or withdraw the entry.

APPENDIX D

Customer-Facing Wording

Adapt these to your own services, language and tone. Keep them short, specific and honest.

Before the wallet opens

> **Verify with your wallet** We will ask your wallet to confirm *[that you are over 18]*. We will not receive *[your date of birth, address or document number]*. We keep *[the result and the time]* for *[30 days]*. You can choose *[to upload a document]* instead.

If the customer declines

> **No problem.** You can verify another way: *[upload a document / visit a counter / contact us]*. It takes about *[x minutes]*.

If the check fails

> **We could not confirm this.** *[This licence has expired.]* You can try another credential or ask a member of our team to help. We have not kept any of the information your wallet shared.

If the wallet is not supported

> **Your wallet could not connect.** This can happen with some wallets and older phones. Please use *[the other route]* instead. Your progress is saved.

Staff script for the counter

- Say what you will ask for and why, before asking.
- Tell the customer what appears on your screen.
- If the check fails, use the referral steps, not your own judgement.
- Never accept a photograph sent by chat in place of the check.
- Record every exception with a reason.

APPENDIX E

Integration Checklist

For the technical lead and the product owner, together.

Scope and design

- ☐ The pilot flow and the exact attributes are fixed and match Appendix B.
- ☐ Wallet verification sits behind one decision point returning pass, fail or refer.
- ☐ The alternative route is built, visible and equally fast.
- ☐ Progress is kept when the customer leaves and returns.

Security

- ☐ A fresh one-time value is used in every request and checked on return.
- ☐ Verification happens on the server.
- ☐ Wallet responses are excluded from logs, analytics and support tools.
- ☐ Certificates and keys are held as secrets with expiry alerts.
- ☐ Trusted-list and status checks are in place and monitored.

Testing

- ☐ Tested on the same device, a second device and in person.
- ☐ Tested on older handsets and with assistive technology.
- ☐ Tested with expired, revoked and untrusted credentials.
- ☐ Tested what happens when the wallet is cancelled mid-flow.

Operations

- ☐ Support has the one-page guide and the four-problem script.
- ☐ The four measures from Chapter 7 are on a dashboard.
- ☐ An incident path exists for a leaked response or a failed certificate.
- ☐ The registration entry matches the live product.

APPENDIX F

90-Day Readiness Tracker

Week	Task	Owner	Due	Done
1	Name owner; list flows (Appendix A)			
2	Classify and minimise (Appendix B)			
3	Confirm legal position and authority			
4	Send twelve vendor questions			
5	Choose pilot flow			
6	Choose route (A, B or C)			
7	Registration pack and notice; short DPIA			
8	Fallback design and support guide			
9	Build or configure			
10	Test with ten people			
11	Limited launch; watch the numbers			
12	Review; expand, adjust or pause			

End-of-quarter review

- Wallet completion rate vs old route: _____
- Fallback rate and main reasons: _____
- Decision (expand / adjust / pause): _____
- What we will change in the register and the registration entry: _____

Glossary

Access certificate. A credential issued to a relying party so a wallet can check it is really who it says it is.

Attestation (electronic attestation of attributes). A signed statement about a person from an issuer, such as a diploma or a licence.

Attribute. A single fact in a credential, such as date of birth.

Credential. A signed digital record, held in a wallet, containing one or more attributes.

Holder. The person who holds credentials in their wallet.

Intended use. The purpose, declared at registration, for which a relying party requests wallet data.

Issuer. The organisation that creates and signs a credential.

mdoc. The mobile document format from ISO 18013-5, also used for digital driving licences.

OpenID4VCI / OpenID4VP. Open standards for issuing credentials into a wallet and for presenting them to a relying party.

PID. Person identification data: the core identity record issued under a Member State's authority.

Registration certificate. A signed object describing what a relying party has registered to request.

Relying party. A business or public body that asks a wallet for data to deliver a service. That is you.

Selective disclosure. Sharing only part of a credential, or a derived answer, while the signature can still be checked.

SD-JWT. A credential format built for selective disclosure.

Strong user authentication. Authentication with at least two independent elements, required by some laws for some sectors.

Trusted list. A published list of issuers and services a framework recognises.

Wallet provider. The organisation that supplies the wallet app to users.

A Note on GDPRGard.eu

If your wallet work touches customer data, the free tools, guides and articles at **gdprgard.eu** can help with the surrounding data-protection tasks: records of processing, impact assessments, breach response and privacy notices. They are a companion resource, not a substitute for advice on your own situation.

About the Author

Zirlandia Milkovic writes practical, plain-English guides on data protection, cyber-security, AI and building a business with confidence. She believes technology should give small businesses more control, not less, and that nobody should need a technical degree to understand their rights or protect their customers.

She is the author of a series of business guides, including *GDPR Made Simple for Women Founders*, and her work focuses on turning complex rules and fast-moving technology into simple steps, checklists and templates that busy people can actually use. She is also behind **GDPRGard**, a growing collection of free GDPR tools, guides and articles for small businesses, available at gdprgard.eu.

The Wallet at Work grew out of a simple observation: businesses are told the European Digital Identity Wallet is coming, and almost nobody explains what a business should decide first. If this guide helped you, an honest review where you bought it helps other readers find it.

Visit **gdprgard.eu** for free tools, articles and updates.

Notes and Sources

1. Regulation (EU) 2024/1183 of 11 April 2024 amending Regulation (EU) No 910/2014 (eIDAS) as regards establishing the European Digital Identity Framework; in force May 2024. Wallet voluntary for individuals, selective disclosure, pseudonyms, user dashboard, no tracking by providers (working knowledge and secondary summaries; article numbers deliberately not cited because the Official Journal text was not read directly).
2. Timeline and acceptance duties: Member States to provide at least one wallet by the end of 2026 (24 December 2026 in several sources; one vendor source gives 31 December); acceptance by regulated private relying parties roughly 36 months after the first implementing acts, i.e. late 2027; very large online platforms on an earlier timetable; Commission acknowledgement that not all countries will be fully ready. Sources: law-firm and vendor briefings seen through search (Arthur Cox, Kennedys, eIDEAS, Start With Identity, Corbado, Fintech Global July 2026). Not checked against the Official Journal.
3. Commission Implementing Regulation (EU) 2025/848 of 6 May 2025 on the registration of wallet-relying parties: declaration of intended use and precise attribute list; requesting undeclared data is a ground for cancellation (Article 6); registration certificates. Seen through search summaries and secondary pages (iGrant.io, EPICENTER.works, EUR-Lex index). An amendment on applicable standards was reported (a source cites Implementing Regulation (EU) 2026/1730, 15 July 2026) and could not be confirmed. The application date of detailed rules is reported inconsistently (one German source says 24 December 2026).
4. Architecture and Reference Framework and related specifications: credential formats SD-JWT VC and ISO/IEC 18013-5 mdoc; OpenID4VCI 1.0 and OpenID4VP 1.0 final; HAIP profile; interoperability events through 2026 (OpenID Foundation EUDI page; eudiw handbook; German developer guide glossary; search summaries). One source claims ARF 3.0.0 was published in July 2026; unconfirmed. PID mandatory attributes listed from working knowledge.
5. Regulation (EU) 2016/679 (GDPR), Articles 5(1)(c) and (e), 6, 9, 13-14, 25, 28, 32, 33, 35 and 44 onward (working knowledge; read the text).
6. European Data Protection Supervisor, formal comments on the draft implementing regulation amending Implementing Regulation (EU) 2025/848, 17 April 2026: intended-use descriptions must be specific enough to verify that requested attributes are necessary and proportionate (seen through search summary; PDF not read).

7. European Accessibility Act, Directive (EU) 2019/882: duties for many consumer-facing digital services from 28 June 2025 (working knowledge; scope should be checked for your service).
8. GDPR Article 33: notification of a personal data breach to the supervisory authority within 72 hours where feasible (working knowledge).
9. Whether a wallet credential satisfies customer-due-diligence or strong-authentication rules in a given sector depends on that sector's law and regulator (for example payment services, AML rules); not analysed here.

Not verified by the author: the exact text and article numbers of Regulation (EU) 2024/1183; the exact wallet and acceptance dates in each Member State; the final text and application date of Implementing Regulation (EU) 2025/848 and its amendments; which wallets exist in which countries on any given day; whether registration certificates are issued in your Member State; current specification versions; and how any named sector regulator will treat wallet credentials. Marta, Adria Drive, Fenix Fitness, Klarheit Energy and all events in the worked examples are fictional.